

Field Report

CVS #8978 - San Antonio

Bid No. 2

Selected Sections: 5400 Cold Formed Metal Framing, 6100 Rough Carpentry, 7210 Building Insulation, 8100 Metal Doors and Frames, 9250 Drywall, 9500 Acoustical Ceilings, 9205 Metal Lath and Trims, 9950 Wall Covering

Selected Typical Areas:

Selected Areas: (unassigned), Sales Floor, Office, Perimeter Framing, Drive Thru Canopy, Exterior Cornice, Exterior Columns, Roof, Restrooms, Hallway # 109

Estimator: **BB - Bryan Bumpus**

Job Class:

Wage Type: **Open**

Job Status: **Pending**

Bid Date/Time: **8/13/2009 12:00:00 PM**

Plans Date: **7/22/2009**

5400 Cold Formed Metal Framing

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
1	Wall Type: 15 A 6.1	3' 0"	42.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		9.24 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 9' (S35818C)		12.08 studs	3' 0" x 16 IN x 1				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		126.00 SF	3' 0" x 1 row	FRM STRU	1.00	293.33	0.43
2	Wall Type: G-1	20' 0"	21.00 LF					
	Stud 3-5/8 18ga Cee, 20' (S35818C)		18.11 studs	20' 0" x 16 IN x 1				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		420.00 SF	20' 0" x 1 row	FRM STRU	1.00	293.33	1.43
	Track 3-5/8 18ga, 10' (T35818)		4.62 pieces	2 rows				
4	Wall Type: D-1	20' 0"	14.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		3.08 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 20' (S35818C)		24.15 studs	20' 0" x 16 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		280.00 SF	20' 0" x 1 row	FRM STRU	1.00	293.33	0.95
10	Wall Type: A-1	20' 0"	68.00 LF					
	Stud 3-5/8 18ga Cee, 20' (S35818C)		58.65 studs	20' 0" x 16 IN x 1				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,360.00 SF	20' 0" x 1 row	FRM STRU	1.00	293.33	4.64
	Track 3-5/8 18ga, 10' (T35818)		14.96 pieces	2 rows				
11	Wall Type: 3 A 1.3	3' 0"	10.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		2.20 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 9' (S35818C)		2.88 studs	3' 0" x 16 IN x 1				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		30.00 SF	3' 0" x 1 row	FRM STRU	1.00	80.00	0.38
13	Soffit (5 A 4.2)	8' 0"	55.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		12.10 pieces	2 rows				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		440.00 SF	8' 0" x 1 row	FRM STRU	1.00	234.67	1.88
15	Soffit (3 A 5.1)	8' 0"	110.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		24.20 pieces	2 rows				
	Screw Pan Head 7/16 Tek (PHT)		0.04 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		880.00 SF	8' 0" x 1 row	FRM STRU	1.00	234.67	3.75
16	Soffit (16 A 5.1)	8' 0"	46.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		20.24 pieces	4 rows				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		368.00 SF	8' 0" x 1 row	FRM STRU	1.00	122.67	3.00
	Track 2-1/2 18ga, 10' (T21218)		10.12 pieces	2 rows				
	Stud 2-1/2 18ga Cee, 8' (S21218C)		19.84 studs	4' 0" x 16 IN x 1				

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
3	Wall Type: F-1	12' 0"	14.00 LF					

Field Report

CVS #8978 - San Antonio

Bid No. 2

5400 Cold Formed Metal Framing

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
	Framing Heavy Gauge Steel / SF (FMHG/SF)		168.00 SF	12' 0" x 1 row	FRM STRU	1.00	391.11	0.43
5	Wall Type: C-1	12' 0"	23.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		276.00 SF	12' 0" x 1 row	FRM STRU	1.00	276.00	1.00
6	Wall Type: B-2	10' 0"	9.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		90.00 SF	10' 0" x 1 row	FRM STRU	1.00	391.11	0.23
7	Wall Type: B-1	10' 0"	21.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		210.00 SF	10' 0" x 1 row	FRM STRU	1.00	391.11	0.54
8	Wall Type: A-2	12' 0"	44.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		528.00 SF	12' 0" x 1 row	FRM STRU	1.00	391.11	1.35
9	Wall Type: A-1	12' 0"	189.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		2,268.00 SF	12' 0" x 1 row	FRM STRU	1.00	391.11	5.80
18	Wall Type: E-1	12' 0"	18.00 LF					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		216.00 SF	12' 0" x 1 row	FRM STRU	1.00	391.11	0.55

Perimeter Framing

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
19	Exterior Framing (5 A5.5)	26' 0"	34.00 LF					
	Track 6 16ga DL, 10' (T616DL)		11.22 pieces	3 rows				
	Stud 6 18ga Cee, 26' (S618C)		29.33 studs	26' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		884.00 SF	26' 0" x 1 row	FRM STRU	1.00	270.77	3.26
20	Exterior Framing (5 A5.2)	24' 0"	72.00 LF					
	Track 6 16ga DL, 10' (T616DL)		23.76 pieces	3 rows				
	Stud 6 18ga Cee, 24' (S618C)		62.10 studs	24' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.03 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,728.00 SF	24' 0" x 1 row	FRM STRU	1.00	270.77	6.38
21	Exterior Framing (6 A 5.5)	24' 0"	48.00 LF					
	Track 6 16ga DL, 10' (T616DL)		15.84 pieces	3 rows				
	Stud 6 18ga Cee, 24' (S618C)		41.40 studs	24' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,152.00 SF	24' 0" x 1 row	FRM STRU	1.00	270.77	4.25
22	Exterior Framing (3 A5.1)	26' 0"	87.00 LF					
	Track 6 16ga DL, 10' (T616DL)		28.71 pieces	3 rows				
	Stud 6 18ga Cee, 26' (S618C)		75.04 studs	26' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.03 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		2,262.00 SF	26' 0" x 1 row	FRM STRU	1.00	270.77	8.35
23	Exterior Framing (1 A5.2)	24' 0"	36.00 LF					
	Track 6 16ga DL, 10' (T616DL)		11.88 pieces	3 rows				
	Stud 6 18ga Cee, 24' (S618C)		31.05 studs	24' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		864.00 SF	24' 0" x 1 row	FRM STRU	1.00	270.77	3.19
24	Exterior Framing (3 A5.2)	24' 0"	124.00 LF					
	Track 6 16ga DL, 10' (T616DL)		40.92 pieces	3 rows				
	Stud 6 18ga Cee, 24' (S618C)		106.95 studs	24' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.04 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		2,976.00 SF	24' 0" x 1 row	FRM STRU	1.00	270.77	10.99

Field Report

CVS #8978 - San Antonio

Bid No. 2

5400 Cold Formed Metal Framing

Perimeter Framing

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
25	Exterior Framing (1 A5.1)	24' 0"	50.00 LF					
	Track 6 16ga DL, 10' (T616DL)		16.50 pieces	3 rows				
	Stud 6 18ga Cee, 24' (S618C)		43.13 studs	24' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,200.00 SF	24' 0" x 1 row	FRM STRU	1.00	270.77	4.43
26	Exterior Framing (1 A5.3)	26' 0"	27.00 LF					
	Track 6 16ga DL, 10' (T616DL)		8.91 pieces	3 rows				
	Stud 6 18ga Cee, 26' (S618C)		23.29 studs	26' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		702.00 SF	26' 0" x 1 row	FRM STRU	1.00	270.77	2.59

Drive Thru Canopy

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
27	Framing ceiling Drive Canopy	18' 0"	22.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		4.84 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 18' (S35818C)		18.98 studs	18' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		396.00 SF	18' 0" x 1 row	FRM STRU	1.00	270.77	1.46
28	Framing ceiling Drive Canopy Upp	8' 0"	60.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		13.20 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 8' (S35818C)		51.75 studs	8' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		480.00 SF	8' 0" x 1 row	FRM STRU	1.00	270.77	1.77

Exterior Cornice

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
29	Cornice Framing	4' 0"	510.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		112.20 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 12' (S35818C)		146.63 studs	4' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.18 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		2,040.00 SF	4' 0" x 1 row	FRM STRU	1.00	213.33	9.56

Exterior Columns

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
30	Fake Columns	20' 0"	96.00 LF					
	Track 3-5/8 18ga, 10' (T35818)		21.12 pieces	2 rows				
	Stud 3-5/8 18ga Cee, 20' (S35818C)		82.80 studs	20' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.03 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,920.00 SF	20' 0" x 1 row	FRM STRU	1.00	234.67	8.18

6100 Rough Carpentry

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
1	Wall Type:15 A 6.1	3' 0"	42.00 LF					
	2x4 SPF Stud Grade & Better, 8' (24SFS2)		5.25 pieces	1' 0" x 16 IN x 1	WOOD FUR	1.00	21.00	0.25
31	Blocking	1' 0"	1,000.00 LF					
	2x6 SPF Stud Grade & Better, 8' (26SFS2)		62.50 pieces	6" x 16 IN x 1	FRAME WD	1.00	10.42	6.00

Roof

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
-----	-----------	--------	----------	-------------	-----------	------	-----------	-----------

Field Report

CVS #8978 - San Antonio

Bid No. 2

6100 Rough Carpentry

Roof

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
32	Plywood Backside of Parapet 4x8x1/2 CDX plywood, 4' x 8' (12CDX)	5' 0"	580.00 LF 95.16 pieces	5' 0" x 1 row	INST. PYLWD	1.00	5.50	16.48

7210 Building Insulation

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
2	Wall Type: G-1 R11x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1116UFR)	20' 0"	21.00 LF 2.46 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.21

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
3	Wall Type: F-1 R11x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1116UFR)	12' 0"	14.00 LF 0.98 rolls	12' 0" x 1 row	BATTS	1.00	187.50	0.08
	Caulk Fire 10 oz, 0.95" (FIRECAULK)		7.78 tubes	2 rows	CAULK	1.00	1,482.11	0.24
	Firesafing 4" batts, 2' x 4' (FIRESAFING)		0.72 bundles		FIRESAFING	1.00	56.25	0.05

Perimeter Framing

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
19	Exterior Framing (5 A5.5) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	26' 0"	34.00 LF 7.97 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.34
20	Exterior Framing (5 A5.2) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	24' 0"	72.00 LF 16.88 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.72
21	Exterior Framing (6 A 5.5) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	24' 0"	48.00 LF 11.25 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.48
22	Exterior Framing (3 A5.1) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	26' 0"	87.00 LF 20.39 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.87
23	Exterior Framing (1 A5.2) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	24' 0"	36.00 LF 8.44 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.36
24	Exterior Framing (3 A5.2) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	24' 0"	124.00 LF 29.06 rolls	20' 0" x 1 row	BATTS	1.00	187.50	1.24
25	Exterior Framing (1 A5.1) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	24' 0"	50.00 LF 7.03 rolls	12' 0" x 1 row	BATTS	1.00	187.50	0.30
26	Exterior Framing (1 A5.3) R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	26' 0"	27.00 LF 6.33 rolls	20' 0" x 1 row	BATTS	1.00	187.50	0.27

8100 Metal Doors and Frames

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
33	Doors Install Door Frame (IDF)		6.00 EA 6.00 EA		DOOR FRAME	1.00	1.28	4.69

9205 Metal Lath and Trims

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
-----	-----------	--------	----------	-------------	-----------	------	-----------	-----------

Field Report

CVS #8978 - San Antonio

Bid No. 2

9205 Metal Lath and Trims

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
12	Suspended Gyp Ceilings		420.00 SF					
	This assembly is a hard lid S/R ceiling using Furring channel (FC78) on 1-1/2" CRC suspended with 9ga hanger wire (HW9) and double wrapped with 18ga Tie wires(TW18).							
	The labor code SRCRC installs the whole suspended framing system including the perimeter wall angle (SRCAGL). Notice the labor cost on the FC78 was reset to -o-.							
	Tie Wire 18ga 25 lb Bundle, 2'-4" long (TW18)		0.03 bundles	48 IN x 2				

9250 Drywall

(unassigned)

Equipment	Height	Quantity	Lab. Code	Crew	Crew Days
0 manlife		3.00			

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
1	Wall Type: 15 A 6.1	3' 0"	42.00 LF					
	5/8" F/S Wallboard, 4' x 10' (X58)		6.62 sheets	3' 0" x 2 rows	HANG LOW	1.00	9.78	0.64
	Screw 1-1/4 Reg (DS114)		0.04 boxes	3' 0" x 12 IN x 2				
2	Wall Type: G-1	20' 0"	21.00 LF					
	Track Slotted Slip 3 5/8" 18 ga, 10' (SST35818)		0.23 bundles	1 row				
	5/8" F/S Wallboard, 4' x 10' (X58)		22.05 sheets	20' 0" x 2 rows	HANG LOW	1.00	9.78	2.15
	Screw 1-1/4 Reg (DS114)		0.13 boxes	20' 0" x 12 IN x 2				
4	Wall Type: D-1	20' 0"	14.00 LF					
	Track Slotted Slip 3 5/8" 18 ga, 10' (SST35818)		0.31 bundles	2 rows				
	5/8" F/S Wallboard, 4' x 10' (X58)		14.70 sheets	20' 0" x 2 rows	HANG LOW	1.00	9.78	1.43
	Screw 1-1/4 Reg (DS114)		0.08 boxes	20' 0" x 12 IN x 2				
10	Wall Type: A-1	20' 0"	68.00 LF					
	Track Slotted Slip 3 5/8" 18 ga, 10' (SST35818)		0.75 bundles	1 row				
	5/8" F/S Wallboard, 4' x 10' (X58)		71.40 sheets	20' 0" x 2 rows	HANG LOW	1.00	9.78	6.95
	Screw 1-1/4 Reg (DS114)		0.41 boxes	20' 0" x 12 IN x 2				
11	Wall Type: 3 A 1.3	3' 0"	10.00 LF					
	5/8" F/S Wallboard, 4' x 10' (X58)		1.58 sheets	3' 0" x 2 rows	HANG LOW	1.00	4.00	0.38
	Screw 1-1/4 Reg (DS114)		0.01 boxes	3' 0" x 12 IN x 2				
13	Soffit (5 A 4.2)	8' 0"	55.00 LF					
	Stud 3-5/8 20ga DW, 8' (S35820)		47.44 studs	8' 0" x 16 IN x 1				
	Pins 3/4 Concrete with brown load (SPC)		0.63 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	5/8" F/S Wallboard, 4' x 10' (X58)		2.89 sheets	2' 0" x 1 row	HANG LOW	1.00	9.78	0.28
	Screw 1-1/4 Reg (DS114)		0.02 boxes	2' 0" x 12 IN x 1				
	Stud 3-5/8 20ga DW, 8' (S35820)		7.91 studs	4' 0" x 48 IN x 1				
15	Soffit (3 A 5.1)	8' 0"	110.00 LF					
	Stud 3-5/8 20ga DW, 12' (S35820)		94.88 studs	12' 0" x 16 IN x 1				
	Pins 3/4 Concrete with brown load (SPC)		1.27 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	5/8" F/S Wallboard, 4' x 10' (X58)		8.66 sheets	3' 0" x 1 row	HANG LOW	1.00	9.78	0.84
	Screw 1-1/4 Reg (DS114)		0.05 boxes	3' 0" x 12 IN x 1				
	Stud 3-5/8 20ga DW, 8' (S35820)		15.81 studs	4' 0" x 48 IN x 1				
16	Soffit (16 A 5.1)	8' 0"	46.00 LF					
	Stud 3-5/8 20ga DW, 12' (S35820)		19.84 studs	3' 0" x 16 IN x 2				

Field Report

CVS #8978 - San Antonio

Bid No. 2

9250 Drywall

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
	Pins 3/4 Concrete with brown load (SPC)		0.53 boxes	24 IN x 2				
	ChopSaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	5/8" F/S Wallboard, 4' x 10' (X58)		6.04 sheets	5' 0" x 1 row	HANG LOW	1.00	7.67	0.75
	Screw 1-1/4 Reg (DS114)		0.03 boxes	5' 0" x 12 IN x 1				
	Stud 3-5/8 20ga DW, 8' (S35820)		6.61 studs	4' 0" x 48 IN x 1				
17	ACT #769		10,470.00 SF					
	Screw 1-1/4 Reg (DS114)		3.14 boxes	12 IN x 2				

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
3	Wall Type: F-1	12' 0"	14.00 LF					
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		0.15 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		0.15 bundles	1 row				
	Stud 3-5/8 20ga DW, 12' (S35820)		12.08 studs	12' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		8.09 sheets	11' 0" x 2 rows	HANG LOW	1.00	9.78	0.79
	Screw 1-1/4 Reg (DS114)		0.05 boxes	11' 0" x 12 IN x 2				
5	Wall Type: C-1	12' 0"	23.00 LF					
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		0.25 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		0.25 bundles	1 row				
	Stud 3-5/8 20ga DW, 12' (S35820)		19.84 studs	12' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		6.64 sheets	11' 0" x 1 row	HANG LOW	1.00	9.78	0.65
	Screw 1-1/4 Reg (DS114)		0.08 boxes	11' 0" x 12 IN x 2				
6	Wall Type: B-2	10' 0"	9.00 LF					
	Track Slotted Slip 6" 20 ga, 10' (SST620)		0.10 bundles	1 row				
	Track 6 20ga DW, 10' (T620)		0.10 bundles	1 row				
	Stud 6 20ga DW, 10' (S620)		7.76 studs	10' 0" x 16 IN x 1				
	5/8" REG Moisture, 4' x 10' (WR58H)		4.59 sheets	10' 0" x 2 rows	HANG LOW	1.00	35.29	0.13
	Screw 1-1/4 Reg (DS114)		0.03 boxes	11' 0" x 12 IN x 2				
	Corner Bead, 10' (CB)		1.20 boxes		TRIM-D/W	1.00	48.00	1.25
	L Bead 5/8", 10' (LB58)		0.20 boxes		TRIM-D/W	1.00	43.20	0.23
7	Wall Type: B-1	10' 0"	21.00 LF					
	Track 3-5/8 20ga DW, 10' (T35820)		0.46 bundles	2 rows				
	Stud 3-5/8 20ga DW, 10' (S35820)		18.11 studs	10' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		10.47 sheets	9' 6" x 2 rows	HANG LOW	1.00	9.78	1.02
	Screw 1-1/4 Reg (DS114)		0.06 boxes	9' 6" x 12 IN x 2				
8	Wall Type: A-2	12' 0"	44.00 LF					
	Track Slotted Slip 6" 20 ga, 10' (SST620)		0.48 bundles	1 row				
	Track 6 20ga DW, 10' (T620)		0.48 bundles	1 row				
	Stud 6 20ga DW, 12' (S620)		37.95 studs	12' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		25.41 sheets	11' 0" x 2 rows	HANG LOW	1.00	9.78	2.48
	Screw 1-1/4 Reg (DS114)		0.15 boxes	11' 0" x 12 IN x 2				
9	Wall Type: A-1	12' 0"	189.00 LF					
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		2.08 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		2.08 bundles	1 row				
	Stud 3-5/8 20ga DW, 12' (S35820)		163.01 studs	12' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		109.15 sheets	11' 0" x 2 rows	HANG LOW	1.00	9.78	10.63
	Screw 1-1/4 Reg (DS114)		0.62 boxes	11' 0" x 12 IN x 2				

Field Report

CVS #8978 - San Antonio

Bid No. 2

9250 Drywall

Office

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
12	Suspended Gyp Ceilings		420.00 SF					
	This assembly is a hard lid S/R ceiling using Furring channel (FC78) on 1-1/2" CRC suspended with 9ga hanger wire (HW9) and double wrapped with 18ga Tie wires(TW18). The labor code SRCRC installs the whole suspended framing system including the perimeter wall angle (SRCAGL). Notice the labor cost on the FC78 was reset to -o-.							
	Galv 1-1/2" 16ga CRC, 10' (CRCGA112)		11.55 pieces	48 IN x 1	9250	1.00	21.00	0.50
	DWC 7/8" 25 ga, 10' (FC78X25)		3.62 bundles	16 IN x 1	FURR	1.00	0.00	0.00
	Hanger Wire 9 ga 50lb Hank, 10'-0 long (HW9)		0.03 bundles	144 IN x 1				
	Frame Sheetrock Ceilings (FMSRC)		420.00 SF	1 row	FRM SRC	1.00	280.00	1.50
	Angle 1-1/2 x1-1/2 20 ga, 10' (SRCAGL)		30.00 pieces					
	5/8" F/S Wallboard, 4' x 10' (X58)		11.03 sheets	1 row	HANG SRC	1.00	9.78	1.07
	Screw 1-1/4 Reg (DS114)		0.06 boxes	12 IN x 1				
18	Wall Type: E-1	12' 0"	18.00 LF					
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		0.20 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		0.20 bundles	1 row				
	Stud 3-5/8 20ga DW, 12' (S35820)		15.53 studs	12' 0" x 16 IN x 1				
	5/8" F/S Wallboard, 4' x 10' (X58)		10.40 sheets	11' 0" x 2 rows	HANG LOW	1.00	9.78	1.01
	Screw 1-1/4 Reg (DS114)		0.06 boxes	11' 0" x 12 IN x 2				

Perimeter Framing

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
19	Exterior Framing (5 A5.5)	26' 0"	34.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.39 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		29.01 pieces	26' 0" x 1 row	DENSGLS	1.00	8.46	3.26
	Screw 1-1/4 Tek (DTS114)		0.27 boxes	26' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		17.85 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	1.74
	Screw 1-1/4 Reg (DS114)		0.10 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		26.78 each	16 IN x 1	FRM WALL	1.00	100.00	0.26
20	Exterior Framing (5 A5.2)	24' 0"	72.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.83 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		56.70 pieces	24' 0" x 1 row	DENSGLS	1.00	8.46	6.38
	Screw 1-1/4 Tek (DTS114)		0.52 boxes	24' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		37.80 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	3.68
	Screw 1-1/4 Reg (DS114)		0.22 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		56.70 each	16 IN x 1	FRM WALL	1.00	100.00	0.54
21	Exterior Framing (6 A 5.5)	24' 0"	48.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.55 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		37.80 pieces	24' 0" x 1 row	DENSGLS	1.00	8.46	4.25
	Screw 1-1/4 Tek (DTS114)		0.35 boxes	24' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		25.20 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	2.45
	Screw 1-1/4 Reg (DS114)		0.14 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		37.80 each	16 IN x 1	FRM WALL	1.00	100.00	0.36
22	Exterior Framing (3 A5.1)	26' 0"	87.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		1.00 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					

Field Report

CVS #8978 - San Antonio

Bid No. 2

9250 Drywall

Perimeter Framing

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		74.22 pieces	26' 0" x 1 row	DENSGLS	1.00	8.46	8.35
	Screw 1-1/4 Tek (DTS114)		0.68 boxes	26' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		45.68 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	4.45
	Screw 1-1/4 Reg (DS114)		0.26 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		68.51 each	16 IN x 1	FRM WALL	1.00	100.00	0.65
23	Exterior Framing (1 A5.2)	24' 0"	36.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.41 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		28.35 pieces	24' 0" x 1 row	DENSGLS	1.00	8.46	3.19
	Screw 1-1/4 Tek (DTS114)		0.26 boxes	24' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		18.90 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	1.84
	Screw 1-1/4 Reg (DS114)		0.11 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		28.35 each	16 IN x 1	FRM WALL	1.00	100.00	0.27
24	Exterior Framing (3 A5.2)	24' 0"	124.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		1.43 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		97.65 pieces	24' 0" x 1 row	DENSGLS	1.00	8.46	10.99
	Screw 1-1/4 Tek (DTS114)		0.89 boxes	24' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		65.10 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	6.34
	Screw 1-1/4 Reg (DS114)		0.37 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		97.65 each	16 IN x 1	FRM WALL	1.00	100.00	0.93
25	Exterior Framing (1 A5.1)	24' 0"	50.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.58 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		19.69 pieces	12' 0" x 1 row	DENSGLS	1.00	8.46	2.22
	Screw 1-1/4 Tek (DTS114)		0.18 boxes	12' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		15.75 sheets	12' 0" x 1 row	HANG LOW	1.00	9.78	1.53
	Screw 1-1/4 Reg (DS114)		0.09 boxes	12' 0" x 12 IN x 1				
	Clip for stud (CLIP)		39.38 each	16 IN x 1	FRM WALL	1.00	100.00	0.38
26	Exterior Framing (1 A5.3)	26' 0"	27.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.31 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		23.03 pieces	26' 0" x 1 row	DENSGLS	1.00	8.46	2.59
	Screw 1-1/4 Tek (DTS114)		0.21 boxes	26' 0" x 12 IN x 2				
	5/8" F/S Wallboard, 4' x 10' (X58)		14.18 sheets	20' 0" x 1 row	HANG LOW	1.00	9.78	1.38
	Screw 1-1/4 Reg (DS114)		0.08 boxes	20' 0" x 12 IN x 1				
	Clip for stud (CLIP)		21.26 each	16 IN x 1	FRM WALL	1.00	100.00	0.20

Drive Thru Canopy

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
27	Framing ceiling Drive Canopy	18' 0"	22.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.25 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		12.99 pieces	18' 0" x 1 row	DENSGLS	1.00	8.46	1.46
	Screw 1-1/4 Tek (DTS114)		0.12 boxes	18' 0" x 12 IN x 2				
	Clip for stud (CLIP)		17.33 each	16 IN x 1	FRM WALL	1.00	100.00	0.17
28	Framing ceiling Drive Canopy Upp	8' 0"	60.00 LF					

Field Report

CVS #8978 - San Antonio

Bid No. 2

9250 Drywall

Drive Thru Canopy

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
	Pins 3/4 Concrete with brown load (SPC)		0.69 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		15.75 pieces	8' 0" x 1 row	DENSGLS	1.00	8.46	1.77
	Screw 1-1/4 Tek (DTS114)		0.14 boxes	8' 0" x 12 IN x 2				
	Clip for stud (CLIP)		47.25 each	16 IN x 1	FRM WALL	1.00	100.00	0.45

Exterior Cornice

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
29	Cornice Framing	4' 0"	510.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		5.87 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	Track 1-5/8 20ga DW, 10' (T15820)		11.22 bundles	2 rows				
	Stud 1-5/8 20ga Dw, 8' (S15820)		109.97 studs	2' 0" x 16 IN x 1				

Exterior Columns

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
30	Fake Columns	20' 0"	96.00 LF					
	Pins 3/4 Concrete with brown load (SPC)		1.10 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					

Roof

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
32	Plywood Backside of Parapet	5' 0"	580.00 LF					
	Screw 1-5/8 Reg (DS158)		1.39 boxes	5' 0" x 12 IN x 2				

Hallway # 109

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
34	FRP Hallway #109	4' 0"	53.00 LF					
	FRP Panels, 4' x 8' (FRP)		7.29 pieces	4' 0" x 1 row				
	FRP Dividers, 10' (FRPDIVIDER)		5.30 pieces	4' 0" x 48 IN x 1				
	FRP bottom starter trim, 10' (FRPBOTTM)		10.60 pieces	2 rows				
	FRP Outside corner, 10' (FRPCRN)		0.10 pieces					
	FRP Inside corner, 10' (FRPICRN)		4.00 pieces					
	FRP Mastic 5 Gal., 1' x 1' (FRPMAST)		0.23 pails	4' 0" x 1 row				
	Labor to install FRP, 4' x 8' (FRPLABOR)		7.29 pieces	4' 0" x 1 row	FRP PANL	2.00	6.63	1.00

9500 Acoustical Ceilings

Sales Floor

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
17	ACT #769		10,470.00 SF					
	Arm 7300-WH Prelude Main-T, 12' (7300WH)		11.45 cartons	48 IN x 1				
	Arm XL7340-WH Prelude 4'-T, 4' (7340WH)		22.90 cartons	24 IN x 1				
	Arm XL7328-WH Prelude 2'-T, 2' (7328WH)		3.66 cartons	300 IN x 1				
	Hanger wire 12 ga 50 lb hank, 12'-0 long (HW12)		6.87 hanks	48 IN x 1	WIRES	1.00	0.00	0.00
	Install 2x4 Grid (IG2X4)		10,470.00 SF	1 row	GRD 2X4	1.00	704.00	14.87
	Arm 7800-WH Wall Angle, 12' (7800WH)		1.59 cartons		ANGLE	1.00	0.00	0.00
	1-1/8 Hard Case Nails (HCN)		0.00 boxes	1 row				
	Fence Staples (FS)		0.00 boxes	1 row				
	Pop Rivets (PR)		10.47 boxes	12 IN x 1				
	Arm A769 Cortega 2x4x5/8" SE, 2' x 4' (A769)		114.52 cartons	1 row	TILE	1.00	88.00	14.87

Field Report

CVS #8978 - San Antonio

Bid No. 2

9950 Wall Covering

Restrooms

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Day	Crew Days
14	FRP Restrooms	8' 0"	63.00 LF					
	FRP Panels, 4' x 8' (FRP)		17.33 pieces	8' 0" x 1 row				
	FRP Dividers, 10' (FRPDIVIDER)		12.60 pieces	8' 0" x 48 IN x 1				
	FRP bottom starter trim, 10' (FRPBOTTM)		12.60 pieces	2 rows				
	FRP Outside corner, 10' (FRPCRN)		1.00 pieces					
	FRP Inside corner, 10' (FRPICRN)		9.00 pieces					
	FRP Mastic 5 Gal., 1' x 1' (FRPMAST)		0.55 pails	8' 0" x 1 row				
	Labor to install FRP, 4' x 8' (FRPLABOR)		17.33 pieces	8' 0" x 1 row	FRP PANL	2.00	7.88	2.00