

# Purchasing Report

CVS #8978 - San Antonio

Bid No. 2

Selected Sections: 5400 Cold Formed Metal Framing, 6100 Rough Carpentry, 7210 Building Insulation, 8100 Metal Doors and Frames, 9250 Drywall, 9500 Acoustical Ceilings, 9205 Metal Lath and Trims, 9950 Wall Covering

Selected Typical Areas:

Selected Areas: (unassigned), Sales Floor, Office, Perimeter Framing, Drive Thru Canopy, Exterior Cornice, Exterior Columns, Roof, Restrooms, Hallway # 109

Estimator: **BB - Bryan Bumpus**

Job Class:

Wage Type: **Open**

Job Status: **Pending**

Bid Date/Time: **8/13/2009 12:00:00 PM**

Plans Date: **7/22/2009**

(unassigned)

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
<b>CAULKING</b>						
Caulk Fire 10 oz, 0.95" (FIRECAULK)	30.80 LF	7.78 tubes	_____	6.00 / container	_____	46.69
<b>EQUIPMENT</b>						
Chopsaw Blade 14" (CHOPSAWBLADE)	0.00 EA	0.00 each	_____	455.00 / 100 EA	_____	0.00
<b>FASTNER</b>						
Screw 1-1/4 Reg (DS114)	51,066.00 EA	6.38 boxes	_____	43.50 / container	_____	277.67
Screw 1-5/8 Reg (DS158)	6,960.00 EA	1.39 boxes	_____	47.00 / container	_____	65.42
Screw 1-1/4 Tek (DTS114)	28,905.60 EA	3.61 boxes	_____	75.00 / container	_____	270.99
Fence Staples (FS)	0.00 EA	0.00 boxes	_____	40.00 / container	_____	0.00
1-1/8 Hard Case Nails (HCN)	0.00 EA	0.00 boxes	_____	75.00 / container	_____	0.00
Hanger wire 12 ga 50 lb hank, 12'-0 long (HW12)	687.09 EA	6.87 hanks	_____	30.10 / container	_____	206.82
Hanger Wire 9 ga 50lb Hank, 10'-0 long (HW9)	2.92 EA	0.03 bundles	_____	30.50 / container	_____	0.89
Screw Pan Head 7/16 Tek (PHT)	4,957.20 EA	0.50 boxes	_____	65.00 / container	_____	32.22
Pop Rivets (PR)	10,470.00 EA	10.47 boxes	_____	20.00 / container	_____	209.40
Pins 3/4 Concrete with brown load (SPC)	1,583.55 EA	15.84 boxes	_____	16.00 / 100 EA	_____	253.37
<b>FRP</b>						
FRP Panels, 4' x 8' (FRP)	787.60 SF	24.61 pieces	_____	820.00 / 1000 SF	_____	645.83
FRP bottom starter trim, 10' (FRPBOTTM)	232.00 LF	23.20 pieces	_____	1.70 / container	_____	39.44
FRP Outside corner, 10' (FRPCRN)	11.00 LF	1.10 pieces	_____	1.70 / piece	_____	1.87
FRP Dividers, 10' (FRPDIVIDER)	179.00 LF	17.90 pieces	_____	1.71 / piece	_____	30.61
FRP Inside corner, 10' (FRPICRN)	130.00 LF	13.00 pieces	_____	1.70 / piece	_____	22.10
FRP Mastic 5 Gal., 1' x 1' (FRPMAST)	787.60 SF	0.79 pails	_____	125.01 / container	_____	98.46
<b>GRID-ACT</b>						
Arm 7300-WH Prelude Main-T, 12' (7300WH)	2,748.38 LF	11.45 cartons	_____	389.00 / 1000 LF	_____	1,069.12
Arm XL7328-WH Prelude 2'-T, 2' (7328WH)	439.74 LF	3.66 cartons	_____	340.00 / 1000 LF	_____	149.51
Arm XL7340-WH Prelude 4'-T, 4' (7340WH)	5,496.75 LF	22.90 cartons	_____	330.00 / 1000 LF	_____	1,813.93
Arm 7800-WH Wall Angle, 12' (7800WH)	800.00 LF	1.59 cartons	_____	252.00 / 1000 LF	_____	201.60
<b>INSULATION</b>						
Firesafing 4" batts, 2' x 4' (FIRESAFING)	23.08 SF	0.72 bundles	_____	680.00 / 1000 SF	_____	15.69
R11x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1116UFR)	588.00 SF	3.45 rolls	_____	170.00 / 1000 SF	_____	99.96
R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	9,160.00 SF	107.34 rolls	_____	270.00 / 1000 SF	_____	2,473.20
<b>LATH</b>						
Tie Wire 18ga 25 lb Bundle, 2'-4" long (TW18)	57.75 EA	0.03 bundles	_____	18.00 / container	_____	0.55
<b>METAL FRAMING</b>						
DWC 7/8" 25 ga, 10' (FC78X25)	362.25 LF	3.62 bundles	_____	200.00 / 1000 LF	_____	72.45
Stud 1-5/8 20ga Dw, 8' (S15820)	879.75 LF	109.97 studs	_____	261.00 / 1000 LF	_____	229.61
Stud 2-1/2 18ga Cee, 8' (S21218C)	158.70 LF	19.84 studs	_____	655.00 / 1000 LF	_____	103.95
Stud 3-5/8 18ga Cee, 8' (S35818C)	414.00 LF	51.75 studs	_____	730.00 / 1000 LF	_____	302.22
Stud 3-5/8 18ga Cee, 9' (S35818C)	134.55 LF	14.95 studs	_____	730.00 / 1000 LF	_____	98.22

# Purchasing Report

CVS #8978 - San Antonio

Bid No. 2

(unassigned)

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
<b>METAL FRAMING</b>						
Stud 3-5/8 18ga Cee, 12' (S35818C)	1,759.50 LF	146.63 studs	_____	730.00 / 1000 LF	_____	1,284.44
Stud 3-5/8 18ga Cee, 18' (S35818C)	341.55 LF	18.98 studs	_____	730.00 / 1000 LF	_____	249.33
Stud 3-5/8 18ga Cee, 20' (S35818C)	3,674.25 LF	183.71 studs	_____	730.00 / 1000 LF	_____	2,682.20
Stud 3-5/8 20ga DW, 8' (S35820)	622.15 LF	77.77 studs	_____	361.00 / 1000 LF	_____	224.60
Stud 3-5/8 20ga DW, 10' (S35820)	181.13 LF	18.11 studs	_____	361.00 / 1000 LF	_____	65.39
Stud 3-5/8 20ga DW, 12' (S35820)	3,901.95 LF	325.16 studs	_____	361.00 / 1000 LF	_____	1,408.60
Stud 6 18ga Cee, 24' (S618C)	6,831.00 LF	284.63 studs	_____	981.00 / 1000 LF	_____	6,701.21
Stud 6 18ga Cee, 26' (S618C)	3,318.90 LF	127.65 studs	_____	981.00 / 1000 LF	_____	3,255.84
Stud 6 20ga DW, 10' (S620)	77.63 LF	7.76 studs	_____	500.00 / 1000 LF	_____	38.81
Stud 6 20ga DW, 12' (S620)	455.40 LF	37.95 studs	_____	500.00 / 1000 LF	_____	227.70
Track Slotted Slip 3 5/8" 18 ga, 10' (SST35818)	128.70 LF	1.29 bundles	_____	1,767.00 / 1000 LF	_____	227.41
Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)	268.40 LF	2.68 bundles	_____	1,633.00 / 1000 LF	_____	438.30
Track Slotted Slip 6" 20 ga, 10' (SST620)	58.30 LF	0.58 bundles	_____	2,110.00 / 1000 LF	_____	123.01
Track 1-5/8 20ga DW, 10' (T15820)	1,122.00 LF	11.22 bundles	_____	231.00 / 1000 LF	_____	259.18
Track 2-1/2 18ga, 10' (T21218)	101.20 LF	10.12 pieces	_____	480.00 / 1000 LF	_____	48.58
Track 3-5/8 18ga, 10' (T35818)	2,420.00 LF	242.00 pieces	_____	595.00 / 1000 LF	_____	1,439.90
Track 3-5/8 20ga DW, 10' (T35820)	314.60 LF	3.15 bundles	_____	341.00 / 1000 LF	_____	107.28
Track 6 16ga DL, 10' (T616DL)	1,577.40 LF	157.74 pieces	_____	1,050.00 / 1000 LF	_____	1,656.27
Track 6 20ga DW, 10' (T620)	58.30 LF	0.58 bundles	_____	450.00 / 1000 LF	_____	26.24
<b>METAL</b>						
Clip for stud (CLIP)	441.00 EA	441.00 each	_____	5.00 / container	_____	2,205.00
Galv 1-1/2" 16ga CRC, 10' (CRCGA112)	115.50 LF	11.55 pieces	_____	395.00 / 1000 LF	_____	45.62
Angle 1-1/2 x1-1/2 20 ga, 10' (SRCAGL)	300.00 LF	30.00 pieces	_____	255.00 / 1000 LF	_____	76.50
<b>SHEATHING</b>						
GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)	12,646.20 SF	395.19 pieces	_____	567.00 / 1000 SF	_____	7,170.40
<b>TILE</b>						
Arm A769 Cortega 2x4x5/8" SE, 2' x 4' (A769)	10,993.50 SF	114.52 cartons	_____	330.00 / 1000 SF	_____	3,627.86
<b>TRIM DRYWALL</b>						
Corner Bead, 10' (CB)	600.00 LF	1.20 boxes	_____	100.00 / container	_____	120.00
L Bead 5/8", 10' (LB58)	100.00 LF	0.20 boxes	_____	50.00 / container	_____	10.00
<b>WALLBOARD</b>						
5/8" REG Moisture, 4' x 10' (WR58H)	183.60 SF	4.59 sheets	_____	260.00 / 1000 SF	_____	47.74
5/8" F/S Wallboard, 4' x 10' (X58)	22,222.20 SF	555.56 sheets	_____	170.00 / 1000 SF	_____	3,777.77
<b>WOOD</b>						
4x8x1/2 CDX plywood, 4' x 8' (12CDX)	3,045.00 SF	95.16 pieces	_____	32.00 / piece	_____	3,045.00
2x4 SPF Stud Grade & Better, 8' (24SFS2)	42.00 LF	5.25 pieces	_____	10.00 / piece	_____	52.50
2x6 SPF Stud Grade & Better, 8' (26SFS2)	500.00 LF	62.50 pieces	_____	16.00 / piece	_____	1,000.00

Equipment	Quantity	Ordered	Quoted	Paid	Total
<b>EQUIPMENT</b>					
manlife	3.00	_____	750.00	_____	2,250.00