

Field Report

McDonalds - Killeen

Bid No. 37

Selected Sections: 05400 Cold Formed Metal Framing, 06100 Rough Carpentry, 07210 Building Insulation, 07820 Water-resistive Barriers,
 08100 Metal Doors and Frames, 09000 Scaffolding, 09110 Interior Metal Framing, 09205 Metal Lath and Trims, 09250 Drywall, 09500
 Acoustical Ceilings, 09950 Wall Covering

Selected Typical Areas:

Selected Areas: (unassigned)

Estimator:
 Job Class:
 Wage Type: **Open**

Job Status:
 Bid Date/Time: **4/2/2010 12:00:00 PM**
 Plans Date: **4/2/2010**

05400 Cold Formed Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
1	Detail 5 on A 5.3	18' 0"	94.75 LF					
	Lay Out & Botton Track (BTLO)		94.75 LF	1 row	FRM WALL	1.00	18.00	5.26
	Track 6 18ga DL, 10' (T618DL)		41.28 pieces	4 rows				
	Stud 6 20ga Cee, 18' (S620C)		81.39 studs	18' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.17 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		1.04 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,705.50 SF	18' 0" x 1 row	FRM STRU	1.00	33.82	50.43
	Screw 1-1/4 Reg (DS114)		0.24 boxes	13' 6" x 12 IN x 1				
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.92 each					
2	Detail 6 on A 5.3	12' 0"	5.33 LF					
	Lay Out & Botton Track (BTLO)		5.33 LF	1 row	FRM WALL	1.00	18.00	0.30
	Track 6 18ga DL, 10' (T618DL)		1.16 pieces	2 rows				
	Stud 6 20ga Cee, 12' (S620C)		4.42 studs	12' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.06 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		64.00 SF	12' 0" x 1 row	FRM STRU	1.00	33.82	1.89
	Chopsaw Blade 14" (CHOPSAWBLADE)		1.00 each					
3	Detail 5 on A 5.0	18' 0"	65.92 LF					
	Lay Out & Botton Track (BTLO)		65.92 LF	1 row	FRM WALL	1.00	18.00	3.66
	Track 6 18ga DL, 10' (T618DL)		14.36 pieces	2 rows				
	Stud 6 20ga Cee, 18' (S620C)		56.62 studs	18' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.12 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.72 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		1.00 each					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,186.50 SF	18' 0" x 1 row	FRM STRU	1.00	33.82	35.08
4	Detail 7 on A 5.1 & A5.2	18' 0"	49.92 LF					
	Lay Out & Botton Track (BTLO)		49.92 LF	1 row	FRM WALL	1.00	18.00	2.77
	Track 6 18ga DL, 10' (T618DL)		21.75 pieces	4 rows				
	Stud 6 20ga Cee, 18' (S620C)		42.88 studs	18' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.09 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.55 boxes	24 IN x 2				
	Chopsaw Blade 14" (CHOPSAWBLADE)		5.00 each					
	Framing Heavy Gauge Steel / SF (FMHG/SF)		898.50 SF	18' 0" x 1 row	FRM STRU	1.00	33.82	26.57
5	Detail 6 on A 5.2	4' 0"	6.58 LF					
	Track 6 18ga DL, 10' (T618DL)		1.43 pieces	2 rows				
	Stud 6 20ga Cee, 8' (S620C)		3.64 studs	4' 0" x 16 IN x 1				

Field Report

McDonalds - Killeen

Bid No. 37

05400 Cold Formed Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		26.33 SF	4' 0" x 1 row	FRM STRU	1.00	33.82	0.78
6	Detail 2 on A 3.1	20' 0"	71.58 LF					
	Track 6 18ga DL, 10' (T618DL)		15.59 pieces	2 rows				
	Stud 6 20ga Cee, 20' (S620C)		61.74 studs	20' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.13 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,431.67 SF	20' 0" x 1 row	FRM STRU	1.00	33.82	42.33
7	Detail 7 on A 5.0	18' 0"	44.25 LF					
	Track 6 18ga DL, 10' (T618DL)		9.64 pieces	2 rows				
	Stud 6 20ga Cee, 18' (S620C)		38.01 studs	18' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.08 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		796.50 SF	18' 0" x 1 row	FRM STRU	1.00	33.82	23.55
8	Detail 6 on A 5.0	13' 0"	10.50 LF					
	Track 6 18ga DL, 10' (T618DL)		2.29 pieces	2 rows				
	Stud 6 20ga Cee, 13' (S620C)		8.13 studs	13' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		136.50 SF	13' 0" x 1 row	FRM STRU	1.00	33.82	4.04
9	Detail 5 on A 5.1	18' 0"	8.00 LF					
	Lay Out & Botton Track (BTLO)		8.00 LF	1 row	FRM WALL	1.00	18.00	0.44
	Track 6 18ga DL, 10' (T618DL)		5.23 pieces	6 rows				
	Stud 6 20ga Cee, 18' (S620C)		13.74 studs	18' 0" x 16 IN x 2				
	Screw Pan Head 7/16 Tek (PHT)		0.01 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.09 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		288.00 SF	18' 0" x 2 rows	FRM STRU	1.00	33.82	8.52
	Chopsaw Blade 14" (CHOPSAWBLADE)		5.00 each					
28	Detail 10 on A4.1	15' 0"	45.73 LF					
	Lay Out & Botton Track (BTLO)		45.73 LF	1 row	FRM WALL	1.00	18.00	2.54
	Track 8 18ga DL, 10' (T818DL)		9.77 pieces	2 rows				
	Stud 8 18ga Cee, 15' (S818C)		52.51 studs	15' 0" x 12 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.08 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.50 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		686.00 SF	15' 0" x 1 row	FRM STRU	1.00	33.82	20.28
29	Framing for Crickets	5' 0"	221.56 LF					
	Lay Out & Botton Track (BTLO)		221.56 LF	1 row	FRM WALL	1.00	18.00	12.31
	Track 3-5/8 20ga DW, 10' (T35820)		4.69 bundles	2 rows				
	Stud 3-5/8 20ga Cee, 10' (S35820C)		95.21 studs	5' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.39 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		2.42 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		1,107.78 SF	5' 0" x 1 row	FRM STRU	1.00	33.82	32.76
35	Detail 5 on A 5.2	12' 0"	10.00 LF					
	Lay Out & Botton Track (BTLO)		10.00 LF	1 row	FRM WALL	1.00	18.00	0.56
	Track 6 18ga DL, 10' (T618DL)		2.18 pieces	2 rows				
	Stud 6 20ga Cee, 12' (S620C)		8.29 studs	12' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.02 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.11 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		120.00 SF	12' 0" x 1 row	FRM STRU	1.00	33.82	3.55

Field Report

McDonalds - Killeen

Bid No. 37

05400 Cold Formed Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
38	Detail 1 on A 3.1	5' 0"	39.87 LF					
	Lay Out & Botton Track (BTLO)		39.87 LF	1 row	FRM WALL	1.00	18.00	2.21
	Track 6 18ga DL, 10' (T618DL)		17.37 pieces	4 rows				
	Stud 6 20ga Cee, 10' (S620C)		17.19 studs	5' 0" x 16 IN x 1				
	Screw Pan Head 7/16 Tek (PHT)		0.07 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.44 boxes	24 IN x 2				
	Framing Heavy Gauge Steel / SF (FMHG/SF)		199.34 SF	5' 0" x 1 row	FRM STRU	1.00	33.82	5.89
	Screw 1-1/4 Reg (DS114)		0.10 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		13.49 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	6.12
	Chopsaw Blade 14" (CHOPSAWBLADE)		1.00 each					

06100 Rough Carpentry

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
1	Detail 5 on A 5.3	18' 0"	94.75 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		24.08 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	1.52
	2x6 SPF Stud Grade & Better PT (LEEDS), 8' (26SFSPT)		11.84 pieces	1' 0" x 16 IN x 1	BLOCK	1.00	15.63	0.76
2	Detail 6 on A 5.3	12' 0"	5.33 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		1.36 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.09
	2x6 SPF Stud Grade & Better PT (LEEDS), 8' (26SFSPT)		0.67 pieces	1' 0" x 16 IN x 1	BLOCK	1.00	15.63	0.04
3	Detail 5 on A 5.0	18' 0"	65.92 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		16.75 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	1.05
	2x6 SPF Stud Grade & Better PT (LEEDS), 8' (26SFSPT)		8.24 pieces	1' 0" x 16 IN x 1	BLOCK	1.00	15.63	0.53
4	Detail 7 on A 5.1 & A5.2	18' 0"	49.92 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		12.69 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.80
	2x6 SPF Stud Grade & Better PT (LEEDS), 8' (26SFSPT)		6.24 pieces	1' 0" x 16 IN x 1	BLOCK	1.00	15.63	0.40
5	Detail 6 on A 5.2	4' 0"	6.58 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		1.67 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.11
8	Detail 6 on A 5.0	13' 0"	10.50 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		2.67 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.17
9	Detail 5 on A 5.1	18' 0"	8.00 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		2.03 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.13
	2x6 SPF Stud Grade & Better PT (LEEDS), 9' (26SFSPT)		16.00 pieces	18' 0" x 16 IN x 1	BLOCK	1.00	13.89	1.15
17	Framing for Counter	4' 0"	26.00 LF					
	4x8x1/2 CDX plywood, 4' x 8' (12CDX)		3.39 pieces	4' 0" x 1 row	INST. PYLWD	1.00	0.69	4.73
30	FRP	9' 0"	284.52 LF					
	4x8x1/2 CDX plywood, 4' x 8' (12CDX)		83.39 pieces	9' 0" x 1 row	INST. PYLWD	1.00	0.69	116.39
33	Fire Blocking	1' 0"	464.83 LF					
	2x6 SPF Stud Grade & Better FRT, 8' (26SFSFRT)		58.37 pieces	1' 0" x 16 IN x 1	BLOCK	1.00	5.00	11.62

Field Report

McDonalds - Killeen

Bid No. 37

06100 Rough Carpentry

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
34	FRP & Plywood at Order sign	4' 0"	30.00 LF					
	4x8x1/2 CDX F/R plywood, 4' x 8' (12CDXFR)		7.86 pieces	4' 0" x 2 rows	INST. PYLWD	1.00	0.69	10.91
	Screw 1-5/8 Reg (DS158)		0.05 boxes	4' 0" x 12 IN x 2				
35	Detail 5 on A 5.2	12' 0"	10.00 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		2.54 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.16
38	Detail 1 on A 3.1	5' 0"	39.87 LF					
	2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)		10.13 pieces	1' 0" x 16 IN x 2	BLOCK	1.00	15.63	0.64

07210 Building Insulation

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
1	Detail 5 on A 5.3	18' 0"	94.75 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		15.78 rolls	14' 0" x 1 row	BATTS	1.00	23.44	5.31
2	Detail 6 on A 5.3	12' 0"	5.33 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		0.38 rolls	6' 0" x 1 row	BATTS	1.00	23.44	0.13
3	Detail 5 on A 5.0	18' 0"	65.92 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		10.98 rolls	14' 0" x 1 row	BATTS	1.00	23.44	3.69
4	Detail 7 on A 5.1 & A5.2	18' 0"	49.92 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		8.31 rolls	14' 0" x 1 row	BATTS	1.00	23.44	2.80
5	Detail 6 on A 5.2	4' 0"	6.58 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		0.00 rolls	4' 0"	BATTS	1.00	23.44	0.00
6	Detail 2 on A 3.1	20' 0"	71.58 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		0.00 rolls	14' 0"	BATTS	1.00	23.44	0.00
7	Detail 7 on A 5.0	18' 0"	44.25 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		0.00 rolls	14' 0"	BATTS	1.00	23.44	0.00
8	Detail 6 on A 5.0	13' 0"	10.50 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		0.00 rolls	14' 0"	BATTS	1.00	23.44	0.00
9	Detail 5 on A 5.1	18' 0"	8.00 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		1.33 rolls	14' 0" x 1 row	BATTS	1.00	23.44	0.45
11	Wall Type: A1	14' 0"	34.03 LF					
	R13x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1316UFR)		3.13 rolls	14' 0" x 1 row	BATTS	1.00	23.44	1.91
16	Wall Type: B1	14' 0"	13.58 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		2.26 rolls	14' 0" x 1 row	BATTS	1.00	23.44	0.76
35	Detail 5 on A 5.2	12' 0"	10.00 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		1.67 rolls	14' 0" x 1 row	BATTS	1.00	23.44	0.56
38	Detail 1 on A 3.1	5' 0"	39.87 LF					
	R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)		6.64 rolls	14' 0" x 1 row	BATTS	1.00	23.44	2.23

Field Report

McDonalds - Killeen

Bid No. 37

07820 Water-resistive Barriers

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
1	Detail 5 on A 5.3	18' 0"	94.75 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	18' 0" x 1 row	VAPOR	1.00	0.11	11.37
2	Detail 6 on A 5.3	12' 0"	5.33 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	12' 0" x 1 row	VAPOR	1.00	0.11	0.43
3	Detail 5 on A 5.0	18' 0"	65.92 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	18' 0" x 1 row	VAPOR	1.00	0.11	7.91
4	Detail 7 on A 5.1 & A5.2	18' 0"	49.92 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	18' 0" x 1 row	VAPOR	1.00	0.11	5.99
5	Detail 6 on A 5.2	4' 0"	6.58 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	4' 0"	VAPOR	1.00	0.11	0.00
6	Detail 2 on A 3.1	20' 0"	71.58 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	20' 0"	VAPOR	1.00	0.11	0.00
7	Detail 7 on A 5.0	18' 0"	44.25 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	18' 0"	VAPOR	1.00	0.11	0.00
8	Detail 6 on A 5.0	13' 0"	10.50 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	13' 0"	VAPOR	1.00	0.11	0.00
9	Detail 5 on A 5.1	18' 0"	8.00 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls	18' 0" x 1 row	VAPOR	1.00	0.11	0.96
35	Detail 5 on A 5.2	12' 0"	10.00 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls		VAPOR	1.00	0.11	0.00
38	Detail 1 on A 3.1	5' 0"	39.87 LF					
	Tyvek house wrap / Roll, 9' x 150' (TYVEK)		0.00 rolls		VAPOR	1.00	0.11	0.01

08100 Metal Doors and Frames

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
36	Door Frames		9.00 EA					
	Install Door Frame (IDF)		9.00 EA		DOOR FRAME	1.00	0.12	77.14

09000 Scaffolding

(unassigned)

Equipment	Height	Quantity	Lab. Code	Crew	Crew Hours
0 boom-lift		4.00			
0 man-lift		4.00			

09110 Interior Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
10	Wall Type: A	14' 0"	190.50 LF					
	Lay Out & Botton Track (BTLO)		190.50 LF	1 row	FRM WALL	1.00	18.00	10.58
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		2.51 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		4.03 bundles	2 rows				
	Stud 3-5/8 20ga DW, 14' (S35820)		163.90 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.36 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		2.08 boxes	24 IN x 2				
	Frame interior walls (FMSF)		2,666.99 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	64.32
11	Wall Type: A1	14' 0"	34.03 LF					

Field Report

McDonalds - Killeen

Bid No. 37

09110 Interior Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Lay Out & Botton Track (BTLO)		34.03 LF	1 row	FRM WALL	1.00	18.00	1.89
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		0.45 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		0.72 bundles	2 rows				
	Stud 3-5/8 20ga DW, 14' (S35820)		29.28 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.06 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.37 boxes	24 IN x 2				
	Frame interior walls (FMSF)		476.48 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	11.49
12	Wall Type: B	14' 0"	78.50 LF					
	Lay Out & Botton Track (BTLO)		78.50 LF	1 row	FRM WALL	1.00	18.00	4.36
	Track Slotted Slip 6" 20 ga, 10' (SST620)		1.91 bundles	1 row				
	Track 6 20ga DW, 10' (T620)		1.91 bundles	2 rows				
	Stud 6 20ga DW, 14' (S620)		66.80 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.15 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.86 boxes	24 IN x 2				
	Frame interior walls (FMSF)		1,099.04 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	26.51
13	Wall Type: C	14' 0"	46.83 LF					
	Lay Out & Botton Track (BTLO)		46.83 LF	1 row	FRM WALL	1.00	18.00	2.60
	Track 8 20ga DW, 10' (T820)		4.85 bundles	2 rows				
	Stud 8 20ga DW, 14' (S820)		38.78 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.09 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.51 boxes	24 IN x 2				
	Frame interior walls (FMSF)		655.67 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	15.81
14	Wall Type: D1	4' 0"	14.39 LF					
	Lay Out & Botton Track (BTLO)		14.39 LF	1 row	FRM WALL	1.00	18.00	0.80
	Track 3-5/8 20ga DW, 10' (T35820)		0.30 bundles	2 rows				
	Stud 3-5/8 20ga DW, 8' (S35820)		6.17 studs	4' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.03 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.16 boxes	24 IN x 2				
	Frame interior walls (FMSF)		57.55 SF	4' 0" x 1 row	FRM WALL	1.00	41.46	1.39
15	Wall Type: A (D/W 1 side)	14' 0"	15.49 LF					
	Lay Out & Botton Track (BTLO)		15.49 LF	1 row	FRM WALL	1.00	18.00	0.86
	Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)		0.20 bundles	1 row				
	Track 3-5/8 20ga DW, 10' (T35820)		0.33 bundles	2 rows				
	Stud 3-5/8 20ga DW, 14' (S35820)		13.33 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.03 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.17 boxes	24 IN x 2				
	Frame interior walls (FMSF)		216.89 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	5.23
16	Wall Type: B1	14' 0"	13.58 LF					
	Lay Out & Botton Track (BTLO)		13.58 LF	1 row	FRM WALL	1.00	18.00	0.75
	Track Slotted Slip 6" 20 ga, 10' (SST620)		0.33 bundles	1 row				
	Track 6 20ga DW, 10' (T620)		0.33 bundles	2 rows				
	Stud 6 20ga DW, 14' (S620)		11.56 studs	14' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.03 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.15 boxes	24 IN x 2				
	Frame interior walls (FMSF)		190.17 SF	14' 0" x 1 row	FRM WALL	1.00	41.46	4.59
17	Framing for Counter	4' 0"	26.00 LF					

Field Report

McDonalds - Killeen

Bid No. 37

09110 Interior Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Lay Out & Botton Track (BTLO)		26.00 LF	1 row	FRM WALL	1.00	18.00	1.44
	Track 3-5/8 20ga DW, 10' (T35820)		1.10 bundles	4 rows				
	Stud 3-5/8 20ga DW, 8' (S35820)		22.28 studs	4' 0" x 16 IN x 2				
	Screw Pan Head A Points (PHA)		0.05 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.28 boxes	24 IN x 2				
	Frame interior walls (FMSF)		207.97 SF	4' 0" x 2 rows	FRM WALL	1.00	15.00	13.86
	3"x3"x48" Wall Stiffner, 3"x3"x48" Wall Stiffner (33WS)		3.67 piece		FRM WALL	1.00	1.13	3.08
20	Framed Ceilings (9' wide)	10' 0"	7.67 LF					
	Lay Out & Botton Track (BTLO)		7.67 LF	1 row	FRM WALL	1.00	18.00	0.43
	Track 6 20ga DW, 10' (T620)		0.19 bundles	2 rows				
	Stud 6 20ga DW, 10' (S620)		6.61 studs	10' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.01 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.08 boxes	24 IN x 2				
	Frame interior walls (FMSF)		76.67 SF	10' 0" x 1 row	FRM WALL	1.00	23.00	3.33
22	Furrdowndown (3 A1.2)	8' 0"	110.83 LF					
	Lay Out & Botton Track (BTLO)		110.83 LF	1 row	FRM WALL	1.00	18.00	6.16
	Track 3-5/8 20ga DW, 10' (T35820)		2.34 bundles	2 rows				
	Stud 3-5/8 20ga DW, 8' (S35820)		95.01 studs	8' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.21 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		1.21 boxes	24 IN x 2				
	Frame interior walls (FMSF)		886.67 SF	8' 0" x 1 row	FRM WALL	1.00	41.46	21.39
23	Detail 8 on A 1.2	12' 0"	26.08 LF					
	Lay Out & Botton Track (BTLO)		26.08 LF	1 row	FRM WALL	1.00	18.00	1.45
	Track 3-5/8 20ga DW, 10' (T35820)		0.55 bundles	2 rows				
	Stud 3-5/8 20ga DW, 12' (S35820)		21.86 studs	12' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.05 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.29 boxes	24 IN x 2				
	Frame interior walls (FMSF)		313.00 SF	12' 0" x 1 row	FRM WALL	1.00	41.46	7.55
24	Detail 8 on A 1.2 (2'wide)	10' 0"	16.42 LF					
	Lay Out & Botton Track (BTLO)		16.42 LF	1 row	FRM WALL	1.00	18.00	0.91
	Track 3-5/8 20ga DW, 10' (T35820)		0.35 bundles	2 rows				
	Stud 3-5/8 20ga DW, 10' (S35820)		13.91 studs	10' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.03 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.18 boxes	24 IN x 2				
	Frame interior walls (FMSF)		164.17 SF	10' 0" x 1 row	FRM WALL	1.00	41.46	3.96
25	Furrdowndown (2 A1.2)	8' 0"	42.90 LF					
	Lay Out & Botton Track (BTLO)		42.90 LF	1 row	FRM WALL	1.00	18.00	2.38
	Track 3-5/8 20ga DW, 10' (T35820)		0.91 bundles	2 rows				
	Stud 3-5/8 20ga DW, 8' (S35820)		36.78 studs	8' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.08 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.47 boxes	24 IN x 2				
	Frame interior walls (FMSF)		343.24 SF	8' 0" x 1 row	FRM WALL	1.00	41.46	8.28
26	Detail 8 on A 1.2 (1'wide)	10' 0"	10.50 LF					
	Lay Out & Botton Track (BTLO)		10.50 LF	1 row	FRM WALL	1.00	18.00	0.58
	Track 3-5/8 20ga DW, 10' (T35820)		0.22 bundles	2 rows				
	Stud 3-5/8 20ga DW, 10' (S35820)		8.90 studs	10' 0" x 16 IN x 1				

Field Report

McDonalds - Killeen

Bid No. 37

09110 Interior Metal Framing

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Screw Pan Head A Points (PHA)		0.02 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.11 boxes	24 IN x 2				
	Frame interior walls (FMSF)		105.00 SF	10' 0" x 1 row	FRM WALL	1.00	41.46	2.53
27	Framed Ceilings (4' wide)	4' 0"	9.00 LF					
	Lay Out & Botton Track (BTLO)		9.00 LF	1 row	FRM WALL	1.00	18.00	0.50
	Track 3-5/8 20ga DW, 10' (T35820)		0.19 bundles	2 rows				
	Stud 3-5/8 20ga DW, 8' (S35820)		3.86 studs	4' 0" x 16 IN x 1				
	Screw Pan Head A Points (PHA)		0.02 boxes	16 IN x 4				
	Pins 3/4 Concrete with brown load (SPC)		0.10 boxes	24 IN x 2				
	Frame interior walls (FMSF)		36.00 SF	4' 0" x 1 row	FRM WALL	1.00	23.00	1.57

09205 Metal Lath and Trims

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
37	Suspended Ceilings		388.40 SF					
	Tie Wire 18ga 25 lb Bundle, 2'-4" long (TW18)		0.03 bundles	48 IN x 2				

09250 Drywall

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
1	Detail 5 on A 5.3	18' 0"	94.75 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		32.06 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	14.54
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		55.96 pieces	18' 0" x 1 row	DENSGLS	1.00	1.00	53.30
	Screw 1-5/8 Reg (DS158)		0.78 boxes	18' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		1.55 sheets	6" x 1 row	DURO	1.00	0.38	3.95
	Screw 1-5/8 Reg (DS158)		0.02 boxes	6" x 12 IN x 2				
2	Detail 6 on A 5.3	12' 0"	5.33 LF					
	Screw 1-1/4 Reg (DS114)		0.01 boxes	6' 0" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		0.80 sheets	6' 0" x 1 row	HANG LOW	1.00	2.20	0.36
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		2.10 pieces	12' 0" x 1 row	DENSGLS	1.00	1.00	2.00
	Screw 1-5/8 Reg (DS158)		0.03 boxes	12' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.09 sheets	6" x 1 row	DURO	1.00	0.38	0.22
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
3	Detail 5 on A 5.0	18' 0"	65.92 LF					
	Screw 1-1/4 Reg (DS114)		0.17 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		22.31 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	10.11
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		38.93 pieces	18' 0" x 1 row	DENSGLS	1.00	1.00	37.08
	Screw 1-5/8 Reg (DS158)		0.54 boxes	18' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		1.08 sheets	6" x 1 row	DURO	1.00	0.38	2.75
	Screw 1-5/8 Reg (DS158)		0.02 boxes	6" x 12 IN x 2				
4	Detail 7 on A 5.1 & A5.2	18' 0"	49.92 LF					
	Screw 1-1/4 Reg (DS114)		0.13 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		16.89 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	7.66
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		29.48 pieces	18' 0" x 1 row	DENSGLS	1.00	1.00	28.08
	Screw 1-5/8 Reg (DS158)		0.41 boxes	18' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.82 sheets	6" x 1 row	DURO	1.00	0.38	2.08
	Screw 1-5/8 Reg (DS158)		0.01 boxes	6" x 12 IN x 2				

Field Report

McDonalds - Killeen

Bid No. 37

09250 Drywall

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
5	Detail 6 on A 5.2	4' 0"	6.58 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.07 boxes	24 IN x 2				
	Screw 1-1/4 Reg (DS114)		0.01 boxes	4' 0" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		0.66 sheets	4' 0" x 1 row	HANG LOW	1.00	2.20	0.30
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		0.86 pieces	4' 0" x 1 row	DENSGLS	1.00	1.00	0.82
	Screw 1-5/8 Reg (DS158)		0.01 boxes	4' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.11 sheets	6" x 1 row	DURO	1.00	0.38	0.27
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
6	Detail 2 on A 3.1	20' 0"	71.58 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.78 boxes	24 IN x 2				
	Screw 1-1/4 Reg (DS114)		0.08 boxes	6' 0" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		10.77 sheets	6' 0" x 1 row	HANG LOW	1.00	2.20	4.88
	Chopsaw Blade 14" (CHOPSAWBLADE)		2.24 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		46.98 pieces	20' 0" x 1 row	DENSGLS	1.00	1.00	44.74
	Screw 1-5/8 Reg (DS158)		0.65 boxes	20' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		1.17 sheets	6" x 1 row	DURO	1.00	0.38	2.98
	Screw 1-5/8 Reg (DS158)		0.02 boxes	6" x 12 IN x 2				
7	Detail 7 on A 5.0	18' 0"	44.25 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.48 boxes	24 IN x 2				
	Screw 1-1/4 Reg (DS114)		0.11 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		14.97 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	6.79
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		26.14 pieces	18' 0" x 1 row	DENSGLS	1.00	1.00	24.89
	Screw 1-5/8 Reg (DS158)		0.36 boxes	18' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.72 sheets	6" x 1 row	DURO	1.00	0.38	1.84
	Screw 1-5/8 Reg (DS158)		0.01 boxes	6" x 12 IN x 2				
8	Detail 6 on A 5.0	13' 0"	10.50 LF					
	Pins 3/4 Concrete with brown load (SPC)		0.11 boxes	24 IN x 2				
	Screw 1-1/4 Reg (DS114)		0.01 boxes	4' 0" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		1.05 sheets	4' 0" x 1 row	HANG LOW	1.00	2.20	0.48
	Chopsaw Blade 14" (CHOPSAWBLADE)		0.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		4.48 pieces	13' 0" x 1 row	DENSGLS	1.00	1.00	4.27
	Screw 1-5/8 Reg (DS158)		0.06 boxes	13' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.17 sheets	6" x 1 row	DURO	1.00	0.38	0.44
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
9	Detail 5 on A 5.1	18' 0"	8.00 LF					
	Screw 1-1/4 Reg (DS114)		0.02 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		2.71 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	1.23
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		4.73 pieces	18' 0" x 1 row	DENSGLS	1.00	1.00	4.50
	Screw 1-5/8 Reg (DS158)		0.07 boxes	18' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.13 sheets	6" x 1 row	DURO	1.00	0.38	0.33
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
10	Wall Type: A	14' 0"	190.50 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		128.93 sheets	13' 6" x 2 rows	HANG LOW	1.00	1.80	71.44
	1/2" Durock, 4' x 8' (DURO12)		6.23 sheets	6" x 2 rows	DURO	1.00	0.38	15.87

Field Report

McDonalds - Killeen

Bid No. 37

09250 Drywall

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Screw 1-5/8 Reg (DS158)		0.04 boxes	6" x 12 IN x 2				
11	Wall Type: A1	14' 0"	34.03 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		23.03 sheets	13' 6" x 2 rows	HANG LOW	1.00	1.80	12.76
	1/2" Durock, 4' x 8' (DURO12)		1.11 sheets	6" x 2 rows	DURO	1.00	0.38	2.84
	Screw 1-5/8 Reg (DS158)		0.01 boxes	6" x 12 IN x 2				
12	Wall Type: B	14' 0"	78.50 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		53.13 sheets	13' 6" x 2 rows	HANG LOW	1.00	1.80	29.44
	1/2" Durock, 4' x 8' (DURO12)		2.57 sheets	6" x 2 rows	DURO	1.00	0.38	6.54
	Screw 1-5/8 Reg (DS158)		0.02 boxes	6" x 12 IN x 2				
13	Wall Type: C	14' 0"	46.83 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		14.09 sheets	6' 0" x 2 rows	HANG LOW	1.00	1.80	7.81
	1/2" Durock, 4' x 8' (DURO12)		24.52 sheets	8' 0" x 2 rows	DURO	1.00	0.38	62.44
	Screw 1-5/8 Reg (DS158)		0.17 boxes	8' 0" x 12 IN x 2				
14	Wall Type: D1	4' 0"	14.39 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		2.89 sheets	4' 0" x 2 rows	HANG LOW	1.00	1.80	1.60
	1/2" Durock, 4' x 8' (DURO12)		0.47 sheets	6" x 2 rows	DURO	1.00	0.38	1.20
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
	3"x3"x48" Wall Stiffner, 3"x3"x48" Wall Stiffner (33WS)		4.69 piece		FRM WALL	1.00	1.00	4.43
15	Wall Type: A (D/W 1 side)	14' 0"	15.49 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		5.24 sheets	13' 6" x 1 row	HANG LOW	1.00	1.80	2.90
	1/2" Durock, 4' x 8' (DURO12)		0.25 sheets	6" x 1 row	DURO	1.00	0.38	0.65
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 1				
16	Wall Type: B1	14' 0"	13.58 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		9.19 sheets	13' 6" x 2 rows	HANG LOW	1.00	1.80	5.09
	1/2" Durock, 4' x 8' (DURO12)		0.44 sheets	6" x 2 rows	DURO	1.00	0.38	1.13
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
17	Framing for Counter	4' 0"	26.00 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		2.61 sheets	4' 0" x 1 row	HANG LOW	1.00	1.80	1.44
	1/2" Durock, 4' x 8' (DURO12)		0.85 sheets	6" x 2 rows	DURO	1.00	0.38	2.17
	Screw 1-5/8 Reg (DS158)		0.01 boxes	6" x 12 IN x 2				
	Screw 1-5/8 Reg (DS158)		0.05 boxes	4' 0" x 12 IN x 2				
18	ACT # 1		1,551.56 SF					
	Screw 1-1/4 Reg (DS114)		0.59 boxes	12 IN x 2				
19	Act # 2		2,021.07 SF					
	Screw 1-1/4 Reg (DS114)		0.77 boxes	12 IN x 2				
20	Framed Ceilings (9' wide)	10' 0"	7.67 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		1.92 sheets	10' 0" x 1 row	HANG LOW	1.00	0.80	2.40
	Screw 1-1/4 Reg (DS114)		0.01 boxes	10' 0" x 12 IN x 1				
22	Furrdowndown (3 A1.2)	8' 0"	110.83 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		11.11 sheets	4' 0" x 1 row	HANG LOW	1.00	1.20	9.24
23	Detail 8 on A 1.2	12' 0"	26.08 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		3.92 sheets	6' 0" x 1 row	HANG LOW	1.00	1.20	3.26
24	Detail 8 on A 1.2 (2'wide)	10' 0"	16.42 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		1.65 sheets	4' 0" x 1 row	HANG LOW	1.00	1.20	1.37
25	Furrdowndown (2 A1.2)	8' 0"	42.90 LF					

Field Report

McDonalds - Killeen

Bid No. 37

09250 Drywall

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	1/2" F/S Wallboard, 4' x 10' (X12)		4.30 sheets	4' 0" x 1 row	HANG LOW	1.00	1.20	3.58
26	Detail 8 on A 1.2 (1'wide)	10' 0"	10.50 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		1.05 sheets	4' 0" x 1 row	HANG LOW	1.00	1.20	0.88
27	Framed Ceilings (4' wide)	4' 0"	9.00 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		0.90 sheets	4' 0" x 1 row	HANG LOW	1.00	0.80	1.13
	Screw 1-1/4 Reg (DS114)		0.01 boxes	4' 0" x 12 IN x 1				
28	Detail 10 on A4.1	15' 0"	45.73 LF					
	ChopSaw Blade 14" (CHOPSAWBLADE)		2.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		22.51 pieces	15' 0" x 1 row	DENSGLS	1.00	1.00	21.44
	Screw 1-5/8 Reg (DS158)		0.31 boxes	15' 0" x 12 IN x 2				
29	Framing for Crickets	5' 0"	221.56 LF					
	Screw 1-1/4 Reg (DS114)		0.21 boxes	5' 0" x 12 IN x 1				
	GP Dens-Deck 5/8", 4' x 8' (GPDD)		36.35 pieces	5' 0" x 1 row	DENSGLS	1.00	1.00	34.62
	Screw 1-5/8 Reg (DS158)		0.25 boxes	5' 0" x 12 IN x 1				
30	FRP	9' 0"	284.52 LF					
	1/2" F/S Wallboard, 4' x 10' (X12)		-66.88 sheets		HANG LOW	1.00	2.20	-30.32
32	Durock Swapp	9' 0"	237.42 LF					
	1/2" Durock, 4' x 8' (DURO12)		69.91 sheets	9' 0" x 1 row	DURO	1.00	1.00	66.78
	1/2" F/S Wallboard, 4' x 10' (X12)		-56.26 sheets		HANG LOW	1.00	1.35	-41.57
35	Detail 5 on A 5.2	12' 0"	10.00 LF					
	Screw 1-1/4 Reg (DS114)		0.03 boxes	13' 6" x 12 IN x 1				
	1/2" F/S Wallboard, 4' x 10' (X12)		3.38 sheets	13' 6" x 1 row	HANG LOW	1.00	2.20	1.53
	ChopSaw Blade 14" (CHOPSAWBLADE)		1.00 each					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		3.94 pieces	12' 0" x 1 row	DENSGLS	1.00	1.00	3.75
	Screw 1-5/8 Reg (DS158)		0.05 boxes	12' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.16 sheets	6" x 1 row	DURO	1.00	0.38	0.42
	Screw 1-5/8 Reg (DS158)		0.00 boxes	6" x 12 IN x 2				
37	Suspended Ceilings		388.40 SF					
	Galv 1-1/2" 16ga CRC, 10' (CRCGA112)		10.68 pieces	48 IN x 1				
	DWC 7/8" 25 ga, 10' (FC78X25)		3.35 bundles	16 IN x 1	FURR	1.00	0.00	0.00
	Hanger Wire 9 ga 50lb Hank, 10'-0 long (HW9)		0.03 bundles	144 IN x 1				
	Frame Sheetrock Ceilings (FMSRC)		388.40 SF	1 row	FRM SRC	1.00	26.67	14.57
	Angle 1-1/2 x1-1/2 20 ga, 10' (SRCAGL)		9.30 pieces					
	5/8" F/S Wallboard, 4' x 10' (X58)		10.20 sheets	1 row	HANG SRC	1.00	1.33	7.28
	Screw 1-1/4 Reg (DS114)		0.07 boxes	12 IN x 1				
38	Detail 1 on A 3.1	5' 0"	39.87 LF					
	GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)		6.54 pieces	5' 0" x 1 row	DENSGLS	1.00	1.00	6.23
	Screw 1-5/8 Reg (DS158)		0.09 boxes	5' 0" x 12 IN x 2				
	1/2" Durock, 4' x 8' (DURO12)		0.65 sheets	6" x 1 row	DURO	1.00	0.38	1.66
	Screw 1-5/8 Reg (DS158)		0.01 boxes	6" x 12 IN x 2				

09500 Acoustical Ceilings

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
18	ACT # 1		1,551.56 SF					
	Donn DX24 Main-T, 12' (DX24)		1.68 cartons	48 IN x 1				

Field Report

McDonalds - Killeen

Bid No. 37

09500 Acoustical Ceilings

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
	Donn DX422 4'-T, 4' (DX422)		2.80 cartons	24 IN x 1				
	Donn DX216 2'-T, 2' (DX216)		2.80 cartons	48 IN x 1				
	Hanger wire 12 ga 50 lb hank, 12'-0 long (HW12)		1.12 hanks	48 IN x 1	WIRES	1.00	0.00	0.00
	Install 2x4 Grid (IG2X4)		1,551.56 SF	1 row	GRD 2X4	1.00	48.89	31.74
	Donn M7 Wall Mold 7/8" White, 12' (M7)		0.52 cartons	1 row	ANGLE	1.00	0.00	0.00
	Pop Rivets (PR)		1.68 boxes	12 IN x 1				
	USG 3260 Stipple Vinyl Gyp. 1/2" SQ, 2' x 2' (U3260)		100.84 cartons	1 row	TILE	1.00	12.50	31.03
19	Act # 2		2,021.07 SF					
	Donn DX24 Main-T, 12' (DX24)		2.19 cartons	48 IN x 1				
	Donn DX422 4'-T, 4' (DX422)		3.65 cartons	24 IN x 1				
	Donn DX216 2'-T, 2' (DX216)		3.65 cartons	48 IN x 1				
	Hanger wire 12 ga 50 lb hank, 12'-0 long (HW12)		1.46 hanks	48 IN x 1	WIRES	1.00	0.00	0.00
	Install 2x4 Grid (IG2X4)		2,021.07 SF	1 row	GRD 2X4	1.00	50.00	40.42
	Donn M7 Wall Mold 7/8" White, 12' (M7)		0.64 cartons	1 row	ANGLE	1.00	0.00	0.00
	Pop Rivets (PR)		2.19 boxes	12 IN x 1				
	USG 2130 Radar 5/8" FLB, 2' x 2' (U2130)		34.01 cartons	1 row	TEG TILE	1.00	12.50	40.42

09950 Wall Covering

(unassigned)

No.	Condition	Height	Quantity	Application	Lab. Code	Crew	Pcs./ Hour	Crew Hours
30	FRP	9' 0"	284.52 LF					
	FRP Panels, 4' x 9' (FRP)		76.19 pieces	9' 0" x 1 row				
	FRP Dividers, 10' (FRPDIVIDER)		65.84 pieces	9' 0" x 48 IN x 1				
	FRP bottom starter trim, 10' (FRPBOTTM)		29.04 pieces	1 row				
	FRP Outside corner, 10' (FRPCRN)		6.00 pieces					
	FRP Inside corner, 10' (FRPICRN)		12.00 pieces					
	FRP Mastic 5 Gal., 1' x 1' (FRPMAST)		4.11 pails	9' 0" x 1 row				
	Labor to install FRP, 4' x 8' (FRPLABOR)		88.02 pieces	9' 0" x 1 row	FRP PANL	2.00	1.25	64.02
31	FRP (Counter)	4' 0"	25.50 LF					
	FRP Panels, 4' x 9' (FRP)		3.03 pieces	4' 0" x 1 row				
	FRP Dividers, 10' (FRPDIVIDER)		2.62 pieces	4' 0" x 48 IN x 1				
	FRP bottom starter trim, 10' (FRPBOTTM)		2.60 pieces	1 row				
	FRP Outside corner, 10' (FRPCRN)		0.83 pieces					
	FRP Inside corner, 10' (FRPICRN)		1.66 pieces					
	FRP Mastic 5 Gal., 1' x 1' (FRPMAST)		0.16 pails	4' 0" x 1 row				
	Labor to install FRP, 4' x 8' (FRPLABOR)		3.51 pieces	4' 0" x 1 row	FRP PANL	2.00	1.25	2.55
34	FRP & Plywood at Order sign	4' 0"	30.00 LF					
	FRP Panels, 4' x 9' (FRP)		3.57 pieces	4' 0" x 1 row				
	FRP Dividers, 10' (FRPDIVIDER)		3.09 pieces	4' 0" x 48 IN x 1				
	FRP bottom starter trim, 10' (FRPBOTTM)		3.06 pieces	1 row				
	FRP Mastic 5 Gal., 1' x 1' (FRPMAST)		0.19 pails	4' 0" x 1 row				
	Labor to install FRP, 4' x 8' (FRPLABOR)		4.13 pieces	4' 0" x 1 row	FRP PANL	2.00	0.47	8.00