

BEST Estimating

PO Box 1271, Leander, Texas 78646
 Phone: 512- 843 - 0853 Fax: 512 - 986 - 8117

Purchasing Report**McDonalds - Killeen**

Bid No. 37

Selected Sections: 05400 Cold Formed Metal Framing, 06100 Rough Carpentry, 07210 Building Insulation, 07820 Water-resistive Barriers,
 08100 Metal Doors and Frames, 09000 Scaffolding, 09110 Interior Metal Framing, 09205 Metal Lath and Trims, 09250 Drywall, 09500
 Acoustical Ceilings, 09950 Wall Covering

Selected Typical Areas:

Selected Areas: (unassigned)

Estimator:

Job Class:

Wage Type: **Open**

Job Status:

Bid Date/Time: **4/2/2010 12:00:00 PM**Plans Date: **4/2/2010**

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
EQUIPMENT						
Chopsaw Blade 14" (CHOPSAWBLADE)	19.16 EA	19.16 each	_____	455.00 / 100 EA	_____	87.20
FASTNER						
Screw 1-1/4 Reg (DS114)	20,567.60 EA	2.57 boxes	_____	43.50 / container	_____	111.84
Screw 1-5/8 Reg (DS158)	20,361.35 EA	4.07 boxes	_____	47.00 / container	_____	191.40
Hanger wire 12 ga 50 lb hank, 12'-0 long (HW12)	258.25 EA	2.58 hanks	_____	30.10 / container	_____	77.73
Hanger Wire 9 ga 50lb Hank, 10'-0 long (HW9)	2.70 EA	0.03 bundles	_____	30.50 / container	_____	0.82
Screw Pan Head A Points (PHA)	12,072.88 EA	1.21 boxes	_____	80.00 / container	_____	96.58
Screw Pan Head 7/16 Tek (PHT)	11,935.08 EA	1.19 boxes	_____	65.00 / container	_____	77.58
Pop Rivets (PR)	3,873.73 EA	3.87 boxes	_____	20.00 / container	_____	77.47
Pins 3/4 Concrete with brown load (SPC)	1,440.23 EA	14.40 boxes	_____	16.00 / 100 EA	_____	230.44
FRP						
FRP Panels, 4' x 9' (FRP)	2,980.61 SF	82.79 pieces	_____	900.00 / 1000 SF	_____	2,682.55
FRP bottom starter trim, 10' (FRPBOTTM)	346.99 LF	34.70 pieces	_____	2.25 / container	_____	78.07
FRP Outside corner, 10' (FRPCRN)	68.32 LF	6.83 pieces	_____	2.25 / piece	_____	15.37
FRP Dividers, 10' (FRPDIVIDER)	715.48 LF	71.55 pieces	_____	2.25 / piece	_____	160.98
FRP Inside corner, 10' (FRPICRN)	136.63 LF	13.66 pieces	_____	2.25 / piece	_____	30.74
FRP Mastic 5 Gal., 1' x 1' (FRPMAST)	4,466.24 SF	4.47 pails	_____	125.01 / container	_____	558.32
GRID-ACT						
Donn DX216 2'-T, 2' (DX216)	968.43 LF	6.46 cartons	_____	307.00 / 1000 LF	_____	297.31
Donn DX24 Main-T, 12' (DX24)	1,162.12 LF	3.87 cartons	_____	399.00 / 1000 LF	_____	463.69
Donn DX422 4'-T, 4' (DX422)	1,936.87 LF	6.46 cartons	_____	343.00 / 1000 LF	_____	664.34
Donn M7 Wall Mold 7/8" White, 12' (M7)	555.35 LF	1.16 cartons	_____	265.00 / 1000 LF	_____	147.17
INSULATION						
R13x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1316UFR)	534.57 SF	3.13 rolls	_____	245.00 / 1000 SF	_____	130.97
R19x16x96 U/F Fiberglass Rolls, 1' 4" x 8' (R1916UFR)	4,039.69 SF	47.34 rolls	_____	295.00 / 1000 SF	_____	1,191.71
LATH						
Tie Wire 18ga 25 lb Bundle, 2'-4" long (TW18)	53.41 EA	0.03 bundles	_____	22.00 / container	_____	0.63
METAL FRAMING						
3"x3"x48" Wall Stiffner, 3"x3"x48" Wall Stiffner (33WS)	8.36 EA	8.36 piece	_____	45.00 / 1 EA	_____	376.11
DWC 7/8" 25 ga, 10' (FC78X25)	335.00 LF	3.35 bundles	_____	276.00 / 1000 LF	_____	92.46
Stud 3-5/8 20ga DW, 8' (S35820)	1,312.72 LF	164.09 studs	_____	440.00 / 1000 LF	_____	577.60
Stud 3-5/8 20ga DW, 10' (S35820)	228.05 LF	22.81 studs	_____	440.00 / 1000 LF	_____	100.34
Stud 3-5/8 20ga DW, 12' (S35820)	262.32 LF	21.86 studs	_____	440.00 / 1000 LF	_____	115.42
Stud 3-5/8 20ga DW, 14' (S35820)	2,891.11 LF	206.51 studs	_____	440.00 / 1000 LF	_____	1,272.09
Stud 3-5/8 20ga Cee, 10' (S35820C)	952.11 LF	95.21 studs	_____	664.00 / 1000 LF	_____	632.20
Stud 6 20ga DW, 10' (S620)	66.13 LF	6.61 studs	_____	525.00 / 1000 LF	_____	34.72

Purchasing Report

McDonalds - Killeen

Bid No. 37

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
METAL FRAMING						
Stud 6 20ga DW, 14' (S620)	1,097.02 LF	78.36 studs	_____	525.00 / 1000 LF	_____	575.93
Stud 6 20ga Cee, 8' (S620C)	29.09 LF	3.64 studs	_____	848.00 / 1000 LF	_____	24.67
Stud 6 20ga Cee, 10' (S620C)	171.93 LF	17.19 studs	_____	848.00 / 1000 LF	_____	145.80
Stud 6 20ga Cee, 12' (S620C)	152.60 LF	12.72 studs	_____	848.00 / 1000 LF	_____	129.41
Stud 6 20ga Cee, 13' (S620C)	105.68 LF	8.13 studs	_____	848.00 / 1000 LF	_____	89.61
Stud 6 20ga Cee, 18' (S620C)	4,187.77 LF	232.65 studs	_____	848.00 / 1000 LF	_____	3,551.23
Stud 6 20ga Cee, 20' (S620C)	1,234.81 LF	61.74 studs	_____	848.00 / 1000 LF	_____	1,047.12
Stud 8 18ga Cee, 15' (S818C)	787.69 LF	52.51 studs	_____	1,442.00 / 1000 LF	_____	1,135.85
Stud 8 20ga DW, 14' (S820)	542.98 LF	38.78 studs	_____	989.00 / 1000 LF	_____	537.01
Track Slotted Slip 3 5/8" 20 ga, 10' (SST35820)	316.08 LF	3.16 bundles	_____	1,574.00 / 1000 LF	_____	497.52
Track Slotted Slip 6" 20 ga, 10' (SST620)	223.88 LF	2.24 bundles	_____	1,985.00 / 1000 LF	_____	444.40
Track 3-5/8 20ga DW, 10' (T35820)	1,572.66 LF	15.73 bundles	_____	341.00 / 1000 LF	_____	536.28
Track 6 18ga DL, 10' (T618DL)	1,322.75 LF	132.27 pieces	_____	836.00 / 1000 LF	_____	1,105.82
Track 6 20ga DW, 10' (T620)	242.52 LF	2.43 bundles	_____	450.00 / 1000 LF	_____	109.13
Track 8 18ga DL, 10' (T818DL)	97.70 LF	9.77 pieces	_____	1,200.00 / 1000 LF	_____	117.24
Track 8 20ga DW, 10' (T820)	484.80 LF	4.85 bundles	_____	800.00 / 1000 LF	_____	387.84
METAL						
Galv 1-1/2" 16ga CRC, 10' (CRCGA112)	106.81 LF	10.68 pieces	_____	295.00 / 1000 LF	_____	31.51
Angle 1-1/2 x1-1/2 20 ga, 10' (SRCAGL)	93.00 LF	9.30 pieces	_____	203.00 / 1000 LF	_____	18.88
SHEATHING						
GP Dens-Deck 5/8", 4' x 8' (GPDD)	1,163.17 SF	36.35 pieces	_____	900.00 / 1000 SF	_____	1,046.85
GP Dens-Glass Gold 5/8", 4' x 8' (GPDGG58)	7,764.58 SF	242.64 pieces	_____	500.00 / 1000 SF	_____	3,882.29
TILE						
USG 2130 Radar 5/8" FLB, 2' x 2' (U2130)	2,176.87 SF	34.01 cartons	_____	510.00 / 1000 SF	_____	1,110.20
USG 3260 Stipple Vinyl Gyp. 1/2" SQ, 2' x 2' (U3260)	1,613.43 SF	100.84 cartons	_____	500.00 / 1000 SF	_____	806.72
WALLBOARD						
1/2" Durock, 4' x 8' (DURO12)	3,616.40 SF	113.01 sheets	_____	660.00 / 1000 SF	_____	2,386.82
1/2" F/S Wallboard, 4' x 10' (X12)	10,397.09 SF	259.93 sheets	_____	150.00 / 1000 SF	_____	1,559.56
5/8" F/S Wallboard, 4' x 10' (X58)	407.82 SF	10.20 sheets	_____	175.00 / 1000 SF	_____	71.37
WATERPROOF						
Tyvek house wrap / Roll, 9' x 150' (TYVEK)	3,999.82 SF	0.00 rolls	_____	150.00 / 1000 SF	_____	599.97
WOOD						
4x8x1/2 CDX plywood, 4' x 8' (12CDX)	2,776.71 SF	86.77 pieces	_____	10.56 / piece	_____	916.31
4x8x1/2 CDX F/R plywood, 4' x 8' (12CDXFR)	251.41 SF	7.86 pieces	_____	35.00 / piece	_____	274.98
2x12 SPF Stud Grade & Better FRT, 8' (212SFSFRT)	591.35 LF	73.92 pieces	_____	20.00 / piece	_____	1,478.37
2x6 SPF Stud Grade & Better FRT, 8' (26SFSFRT)	466.99 LF	58.37 pieces	_____	12.00 / piece	_____	700.48
2x6 SPF Stud Grade & Better PT (LEEDS), 9' (26SFSPT)	144.00 LF	16.00 pieces	_____	15.00 / piece	_____	240.00
2x6 SPF Stud Grade & Better PT (LEEDS), 8' (26SFSPT)	215.92 LF	26.99 pieces	_____	15.60 / piece	_____	421.04
EQUIPMENT						
boom-lift	4.00		_____	1,500.00	_____	6,000.00
man-lift	4.00		_____	450.00	_____	1,800.00